



DMC Compound, Corner Dumanlas & Friendship Rd.,  
Bajada, Davao City  
Tel. Nos. 226-3921 / 227-5672 / Fax (082) 221-5295 / 226-3921


**Request for Quotation**

RFQ NO. 17-04-299  
DATE: April 25, 2017

Gentlemen:


This is a request for quotation on item(s) enumerated hereunder, if you are interested and in a position to furnish the same. We shall be glad to have your best price, terms and conditions of delivery submitted not later than 10:30 a.m. on \_\_\_\_\_ addressed to the BAC Chairman, DOST XI, Regional Office No. XI, DOST Bldg., DMC Compound, Bajada, Davao City Marked "REQUEST FOR QUOTATION".

ITEM NO.	QTY	UNIT	ARTICLE / DESCRIPTION	UNIT COST	TOTAL COST
	1	lot	Renovation of Halal Laboratory Specifications: Removal of existing glass walls and doors and replace them with a new 3/8" thick tempered clear glass walls and glass pocket sliding doors with tint. Replacement of wooden doors in the storage and hot room with glass pocket sliding doors with tint. Installation of new glass division and sliding doors with tint in the positive and negative control room. Installation of "Onelab Halal" logo on one side of the glass division. Repair of flooring; Remove and replace all defective floor tiles with 60cm x 60cm synthetic Granite tiles (same with existing tiles). Rewiring of electrical lines for the new floor plan layout. Replacement and provision of additional International convenience sockets/outlets (3 prong, 2 gang) for the Halal lab equipment and airconditioning units. Upgrading of the load capacity of the existing outlets and circuit breakers. Installation of new panel boards and circuit breakers. Demolition of Shower Room's two sides concrete walls and remove its door and replace with plastered/smooth 4" concrete hollow block wall. Elevation of flooring and installation of new tiles (same with existing) in the flooring of shower room. Removal of existing wall tiles, plastering of the affected area with cement finishing, and then painting with the same existing paint color. Demolition of sink. Abandonment of the water line at the removed sink. Provision of additional water line and drain at the negative and positive control room. Installation of new Above Sink Storage Cabinet (approx. 50x25x30", double door, four adjustable shelves) and Under Sink Storage Cabinet (approx. 50x25x27", double door, two drawers with drawer guide on the left, and one layered cabinet on the right). Plastering of the under sink with cement finishing. Installation of 3.5 mm thick Cement Fiber Board Ceiling for the affected area in the repositioning of ceiling lights and the new flooring layout. Painting/repainting of Ceiling and Walls. ** Completion of work must be with in 60 calendar days upon receipt of contract		

  
ALVIN P. JUSTO

SUPPLY & PROPERTY OFFICER

Very truly yours,

  
ELSIE MAE A. SOLIDUM  
BAC Chairperson

Prices of the above offers are certified correct:

Authorized Signature

**IMPORTANT**

When offering substitute or equivalent, specify brand or make. Submit your quotation in envelope closed and pasted by indicating the number of the quotation, date & time of opening. DUE DATE: FIVE (5) WORKING DAYS AFTER RECEIPT OF THIS RFQ. ONLY THE BIDS SUBMITTED ON OR BEFORE THE TIME & DATE SPECIFIED WITH PRICES IN DUPLICATE WILL BE CONSIDERED.

Name of Firm

Address of Firm

Vat  
 Non-vat

DATE RECEIVED : \_\_\_\_\_

Signature

Tax Identification No. (TIN)

Telephone Number